

St. Louis County Masterplan Construction Drawings

Index of Drawings:

- Sheet 1 Title & Index
- Sheet 2 Specifications
- Sheet 3 Specifications (cont.)
- Sheet 4 Specifications (cont.)

GENERAL CONSTRUCTION DETAILS

- Sheet 5 Details
- Sheet 6 Details (cont.)
- Sheet 7 Details (cont.)

DESIGN SECTIONS

- Sheet 8 Level Backslope, No Surchage
- Sheet 9 3:1 Slope Above Wall, No Surchage
- Sheet 10 Level Backslope, 120 psf Live Load Surchage (Residential Driveway)

I am pleased to inform you that the plans submitted for review of the Anchor Brisa 6" Retaining Walls are approved and the new master plan numbers are as follows:

6' high max, 3:1 Max Slope, Compacted Rock Backfill, No Surchage 707-14-79
 6' high max, Level-No Slope, Compacted Rock Backfill, No Surchage 707-14-80
 6' high max, Level-No Slope, Compacted Rock Backfill, 120psf LL Surchage 707-14-81

Please inform your customers of the following procedures they need to follow when applying for a residential retaining wall permit with Saint Louis County:

1. Submit a **completed permit application** form that includes the selected master plan number.
2. Submit **four (4) site plans** showing the location and length of the wall, drawn to scale, with the top-of-wall and bottom-of-wall elevations noted at the ends and midpoint of each wall, at a minimum. Dimension the wall(s) distance from any structures, parking lots, easements and property lines. Show with arrows the existing and proposed direction of site drainage at and around the proposed wall area.
3. Submit **four (4) copy sets** of the approved master plan (10 pages total).
4. Your customers should be made aware that a **Saint Louis County Pre-grading Inspection** may be required to assess any potential major changes on the site grading and drainage when a retaining wall is proposed closer than 10-feet to a property line. Conditions on the site plans submitted may also indicate a Saint Louis County Pre-grading Inspection is needed.

This seal refers to this masterplan only and does not refer to any other plan or design relating to a specific project



Michael James Yount - Engineer
 MCE# PE-2003001121



Masterplan, St. Louis County, Mo.



950 Freeburg Ave
 Belleville, IL 62220
 800-427-6282

Engineering
 Solutions, P.C.

5393 Old Baumgartner Rd
 St Louis, Mo. 63129
 Phone (314) 280-7748

Mo State Certificate of Authority #P00565746

Title & Index

Sheet 1 of 10

General

This masterplan is for Anchor Brisa retaining walls on one or two family residential properties only. These plans shall specify the structural requirements of single tier walls up to six feet in height for the specific applications shown. Retaining walls that support a house or other structure or that apply a surcharge to a house or other structure (including swimming pools and other retaining walls) and walls in contact with water such as lakes, rivers, ponds or creeks or any application outside of these specific design sections and/or soil parameters shown herein, are excluded. The user of this masterplan is responsible for confirming its applicability. Retaining walls not meeting these parameters should be individually engineered. This plan must be used in its entirety. The contractor shall locate & protect all existing utilities, and shall be responsible for all worker and public safety at the retaining wall site. The contractor shall be responsible for compliance with all OSHA regulations. All installation shall be per the retaining wall manufacturer's construction recommendations and/or as noted herein.

Site Plan

All walls requiring a St. Louis County permit shall be shown on a site plan drawn to scale showing the locations of the wall relative to property lines, easements & existing or proposed structures. This site plan shall show elevations along the top and bottom of the wall relative to a on site benchmark. The site plan shall show the ground surface inclinations above and below the wall for a lateral distance of at least 25'. The site plan shall clearly define drainage in the wall area.

Drainage

A drainage design is not part of this masterplan. However drainage is an important component of the complete wall design. When feasible, it is recommended that surface water be diverted to not drain over the top of the wall. A swale or drainage boxes/structures can be used to divert surface water. Any drain piping should be watertight piping to an acceptable outfall below the wall & should not be connected to the perforated drainfile used for internal wall drainage. If it is necessary to direct the water over the top of the wall concentration to one point should be avoided. The owner should expect some periodic maintenance of the soil cap & the soil cover at the toe of the wall being required. Water should not be allowed to pond above the wall.

Guard Rails/Fencing

Non-Wind Loading guard rails/fencing shall be installed above the wall where required per code in accordance with Anchor Retaining Walls specifications. We recommend sonotubes or PVC be installed during wall construction for the fence post bases to prevent the need to excavate into the reinforcing zone material and through the geogrid. Wind loaded fences or vehicular guard rails can affect the retaining wall and should be designed by a qualified engineer.

Materials

The **Leveling Pad** shall be constructed 1" minus crushed limestone compacted to at least 90% modified proctor with minimum dimensions of 6" thick and 24" wide.

Retaining Wall Units shall be Anchor Brisa 6" as manufactured by Building Products. Units must be 8" deep. Concrete wall units shall meet the requirements of ASTM C90-90 and compressive strength shall be a minimum of 3000 psi. The maximum water adsorption shall be limited to 8.0 percent. The concrete shall have adequate freeze thaw resistance in accordance with ASTM 666-90.

ANCHORTM Brisa 6"

Masterplan, St. Louis County, Mo.

**BUILDING
PRODUCTS CORP.**
950 Freeburg Ave
Belleville, IL 62220
800-427-6282

**Engineering
Solutions, P.C.**
5393 Old Baumgartner Rd
St Louis, Mo. 63129
Phone (314) 280-7748
Mo. State Certificate of Authority #P00565746

This seal refers to this masterplan only and does not refer to any other plan or design relating to a specific project



Michael James Yount - Engineer
Mo# PE-2003001121

Specifications

Sheet 2 of 10

Wall Construction

Provide a minimum 6" thick x 24" wide crushed limestone leveling pad centered beneath the base block compacted to at least 90% modified proctor. Install the first course of blocks on the leveling pad, units must be level in all directions & be in complete contact with the leveling pad. Install the next course in a running bond stack. Adjust for setback per course. Continue stacking subsequent courses until the level of the first layer of geogrid is reached. Install draisinle & daylight prior to backfilling. Backfill material shall be placed in maximum 12" lifts and compacted by multiple passes with a vibratory plate compactor. Backfill shall be placed, spread and compacted in such a manner that minimizes wrinkles and movement of the geogrid. During backfill placement only hand operated equipment shall be used in the 4' zone directly behind the wall. The front of the wall shall be backfilled and compacted to finished grade. Filter fabric shall separate the granular backfill from the retained soil and the soil cap. Filter fabric shall not cover the foundation materials. The geogrids shall be cut to the lengths shown and placed in accordance with the tables shown on the design sections. The geogrid shall be orientated so that the direction of maximum strength is perpendicular to the face of the wall. There shall be at least 7" of geogrid between the block layers. The geogrids must be kept taut & level. All geogrid installation shall be in accordance with the manufacturers specifications. Install the soil cap, compact & finish grade for proper drainage per the approved site plan.

Sewer & Utility Trench Backfill

Any excavation to be backfilled within a distance of (2) times the wall height from the wall face must be compacted to at least 90% modified proctor. Any excavations made below the wall should be backfilled with 1" or 2" minus compacted to 90% modified proctor, or as directed by a geotechnical engineer.

Protection of Work

The Owner or Owner's Representative is responsible for ensuring that construction by others adjacent to the wall does not disturb the wall or place temporary construction loads on the wall that exceed design loads, including loads such as water pressure, temporary grades, or equipment loading. Heavy paving or grading equipment shall be kept a minimum of 3 feet behind the back of the wall face. Equipment with wheel loads in excess of 150 psf live load shall not be operated within 10 feet of the face of the retaining wall during construction adjacent to the wall. Care should be taken by the Owner or Owner's Representative to ensure water runoff is directed away from the wall structure until final grading and surface drainage collection systems are completed. Finish grading should be completed in accordance with the approved site development plan. The stability of temporary excavation during wall construction is beyond the scope of this design and is the responsibility of the contractor.

Design Parameters

This design is based on design parameters that must be field verified. This verification should include both existing soils & the new fill material. If actual conditions are of lesser strength or quality than the design parameters redesign or remediation may be required. A pre-construction soils investigation may reduce the risk of discovering poor materials & increasing the overall cost of the project during construction. Global stability is outside the scope of this design.

No changes shall be made to these plans without written approval of Engineering Solutions, P.C.

This seal refers to this masterplan only and does not refer to any other plan or design relating to a specific project



Michael James Yount - Engineer
Mo# PE-2003001121





Engineering Solutions, P.C.
5393 Old Baumgartner Rd
St. Louis, Mo. 63129
Phone (314) 280-7748

Masterplan, St. Louis County, Mo.


Sheet 4 of 10

Specifications
(cont.)



WALL ABUTTING EXISTING STRUCTURE
(NOT TO SCALE)

This seal refers to this masterplan only and does not refer to any other plan or design relating to a specific project



Michael James Yount - Engineer
Mo# PE-2003001124

Typical Details

Sheet 5 of 10

EXISTING STRUCTURE

EXISTING STRUCTURE

NON WIND BEARING FENCE OR RAILING (DESIGNED BY OTHERS)

SLEEVE AND NON-SHRINK GROUT AROUND POST

SLOPE MAY VARY

DEPTH VARIES

GEOSYNTHETIC REINFORCEMENT

FENCE BEHIND WALL DETAIL
(NOT TO SCALE)



CAP BLOCK

BLOCK


EXTEND GEOSYNTHETIC REINFORCEMENT TO WITHIN 1" OF THE LOWER BLOCK FACE

7" MIN

REINFORCEMENT CONNECTION DETAIL
(NOT TO SCALE)



TYPICAL BASE PREPARATION
(NOT TO SCALE)



TYPICAL STEP-UP DETAIL
(NOT TO SCALE)




Engineering Solutions, P.C.
5393 Old Baumgartner Rd
St Louis, Mo. 63129
Phone (314) 280-7748
Mo. State Certificate of Authority #P00565746




ANCHOR™

Brisa 6"

Masterplan, St. Louis County, Mo.



OUTSIDE CURVE WITH REINFORCEMENT
(NOT TO SCALE)



This seal refers to this masterplan only and does not refer to any other plan or design relating to a specific project

MICHAEL JAMES YOUNT
STATE OF MISSOURI
PROFESSIONAL ENGINEER
NUMBER PE-2003001121
Mo# PE-2003001121

Michael James Yount - Engineer
Mo# PE-2003001121

Engineering Solutions, P.C.
5393 Old Baumgartner Rd
St Louis, Mo. 63129
Phone (314) 280-7748
Mo. State Certificate of Authority #P00565746


BUILDING PRODUCTS CORP.
950 Freeburg Ave
Belleville, IL 62220
800-427-6282

ANCHOR™
Brisa 6"
Masterplan, St. Louis County, Mo.

Typical Details
(cont.)

Sheet 6 of 10


PRINCIPLE
REINFORCEMENT
DIRECTION



IN THE "CROSS-OVER AREA" OF REINFORCEMENT, ONE OF THE LAYERS OF REINFORCEMENT SHOULD BE LOWERED OR RAISED ONE COURSE TO ALLOW PLACEMENT OF THE REINFORCEMENT WITH THE PRINCIPLE REINFORCEMENT STRENGTH DIRECTION PROPERLY ORIENTATED. THE REINFORCEMENT SHOULD NOT EXTEND INTO THE SEGMENTAL UNITS ON THE RETURN LEG OF THE 90 DEGREE CORNER.

PRINCIPLE
REINFORCEMENT
DIRECTION

REINFORCEMENT NOT SHOWN FOR CLARITY
REINFORCEMENT H/4 BEYOND
THE CORNER AT
REINFORCEMENT ELEVATIONS



NOTES:
PLACEMENT OF REINFORCEMENT
EXTENSION ON SPECIFIED
REINFORCEMENT ELEVATIONS.

PRINCIPLE
REINFORCEMENT
DIRECTION

ANCHOR DIAMOND PRO BLOCK
90 DEGREE INSIDE CORNER WITH REINFORCEMENT
(NOT TO SCALE)

This seal refers to this masterplan only and does not refer to any other plan or design relating to a specific project



Michael James Yount - Engineer
Mo# PE-2003001121

Engineering Solutions, P.C.
5393 Old Baumgartner Rd
St Louis, Mo. 63129
Phone (314) 280-7748
Mo. State Certificate of Authority #P00565746




ANCHORTM
Brisa 6"

Masterplan, St. Louis County, Mo.

Typical Details
(cont.)

Sheet 7 of 10



**Reinforcing Backfill Table
Slope Above Wall (3:1 max)**

Wall Height (feet) (without cap)	Anchor Brisa (6")	
	# of Geogrid Layers	Geogrid Location (on top of course #)
3.0	2	2,4
4.0	3	1,3,6
5.0	4	1,3,5,8
6.0	5	1,3,5,7,10

ANCHOR™
Brisa 6"
Masterplan, St. Louis County, Mo.

BUILDING PRODUCTS CORP.
950 Freeburg Ave
Belleville, IL 62220
800-477-6282

Engineering Solutions, P.C.
5393 Old Baumgartner Rd
St Louis, Mo. 63129
Phone (314) 280-7748
Mo. State Certificate of Authority #R00565746


Refer to Specifications Sheets 2-4 & Construction Details Sheets 5-7 for Additional Requirements

Michael James Yount - Engineer
Mo# PE-2003001121

Typical Cross Section
3:1 Slope, No Surcharge

Sheet 8 of 10


This seal refers to this masterplan only and does not refer to any other plan or design relating to a specific project



Reinforcing Backfill Table
No Slope Above Wall (5:1 max)

Wall Height (feet) (without cap)	Anchor Brisa (6")	
	# of Geogrid Layers	Geogrid Length (ft)
3.0	1	4.0
4.0	2	4.0
5.0	3	4.5
6.0	4	5.0

This seal refers to this masterplan only and does not refer to any other plan or design relating to a specific project



Refer to Specifications Sheets 2-4 & Construction Details Sheets 5-7 for Additional Requirements


Engineering Solutions, P.C.
 5393 Old Baumgartner Rd
 St Louis, Mo. 63129
 Phone (314) 280-7748
 Mo. State Certificate of Authority #P00565746



ANCHOR™
Brisa 6"

Masterplan, St. Louis County, Mo.

Typical Cross Section
 Level Backslope, No Surcharge



Reinforcing Backfill Table
120 psf Live Load Above Wall (residential driveway)

Wall Height (feet) (without cap)	Anchor Brisa (6")		
	# of Geogrid Layers	Geogrid Location (on top of course #)	Geogrid Length (ft)
3.0	1	3	4.0
4.0	2	3,6	4.0
5.0	3	2,5,8	4.5
6.0	4	2,4,7,10	5.0

This seal refers to this masterplan only and does not refer to any other plan or design relating to a specific project



Typical Cross Section
 Level Backslope, 120 psf Surcharge (Residential Driveway)

Sheet 10 of 10

Refer to Specifications Sheets 2-4 & Construction Details Sheets 5-7 for Additional Requirements

Engineering Solutions, P.C.
 5393 Old Baumgartner Rd
 St Louis, Mo. 63129
 Phone (314) 280-7748
 Mo. State Certificate of Authority #P00565746



ANCHOR™
Brisa 6"
 Masterplan, St. Louis County, Mo.